



TEKCAST INDUSTRIES RI

124 Maple Street • Warwick, RI 02888 USA
 TEL: (401) 785-9500 • FAX: (401) 781-9420
 TOLL FREE: (800) USA-4TEK
 E-MAIL: info@tekcast.com • www.tekcast.com

STANDARD QUOTATION for a complete TEK 12X4"
 Spin-Casting Equipment System for *Metal, Plastic & Wax*
 Maximum part size capability: 5" (127mm) x 4" (102mm) x 3½" (89mm)

COMPLETE TEK 12X4" EQUIPMENT SYSTEM

2-112
with
optional
stand



1-112-AM1



3-160N-1W*



Vulcanizing Frame



Aluminum Spacers

QTY	ITEM NO.	DESCRIPTION	PRICE
1	2-112	ANALOG VULCANIZER (220V) 9-12"(229-457mm) mold up to 4" (102mm) thick; Precision Built, 30-ton; 3 Post Heavy Duty Construction.	\$3,986.00
1	1-112-D1	SERIES 100-D (DIGITAL) "FRONT LOADING" TEKCASTER (110V) 9-12"(229-305mm) mold up to 6"(152mm) thick. Includes Stand. Per Spec.	7,333.00
1	3-160N-1W*	GAS MELTING FURNACE ASSEMBLY (Natural); 160 Lb.(73 Kg) (Max.1000°F/540°C). Includes: DT-3 Automatic Digital Temp. Controller; Thermocouple w/Stainless Protection Tube & Bracket; J/C Combo Gas Solenoid & Safety Valve; Includes Stand. Unit is fully wired (110V), set-up and ready to use.	4,487.00
1	12-190-112	9x1½"(229x38mm) Precision Vulcanizing Frame (Aluminum & Steel)	432.00
1	12-212-112	12x1½"(305x38mm) " " " "	532.00
1	-212-3	12x3"(305x76mm) " " " "	576.00
1	12-409	9x½"(229x12.7mm) Aluminum Spacer	92.00
1	12-509	9x1/4"(229x6.35mm) " "	65.00
2	12-412	12x½"(305x12.7mm) " "	@ \$ 1.15/ea 230.00
1	12-512	12x1/4"(305x6.35mm) " "	102.00
TOTAL TEK 12X4" EQUIPMENT SYSTEM			\$17,835.00
Crating Charges (Furnace, Vulcanizer and Spin-Caster) @ \$200.00/ea.			\$600.00
TOTAL CHARGES (FOB Warwick, RI USA)			\$18,435.00

- Option 1:* Vulcanizer Stand welded heavy steel--\$393.50 ea.
- Option 2:* *If Electric Furnace (230V) is substituted (Includes Magnetic Relay)-add \$535.00 ea.
- Option 3:* *3-160P-1W for use with Liquid Propane (LP) gas--at no extra charge

NOTE: These prices are in US Dollars, exclusive of crating and shipping charges & subject to change without notice.
F.O.B.: Warwick, RI & Weight - 1450 lbs (660 Kg) & 75 Cu. Ft.
TERMS: On new equipment orders--50% Deposit & Balance Net 30 (if credit approved)
ESTIMATED SHIP DATE: 4-6 weeks from receipt of confirmed order.